Cement Corporation of India Limited
Rajban Cement Factory,
Distt. Sirmour (HP)-173029
(AN ISO 9001-2015 CERTIFIED COMPANY)
CIN-U74899DL1965GOI004322

TENDER NOTICE

Email tenders are invited from eligible parties for the following work/items as detailed below.
The offers shall be submitted through email only by superscribing the Tender No. and Name of Work in the subject line of the email.

Tender No.& Scope of work	Qty	EMD by DD (Rs.)	Date of opening for sale	Last date of sale of tender with time.	Last date of Submission of Tender with time.	Date & time of opening of Bid.
RCF/INST/OCEMS/STACK/2026-27 Tender for Calibration of 05 Nos OCEMS analysers and isokinetic stack emission monitoring/testing of Cement Mill, Kiln and Coal Mill stacks for compliance with CPCB per scope of work.	**As defined in scope of work**	**NIL**	07.11.2026 18:15:00 hrs	09.11.2026 15:00:00 hrs	09.11.2026 15:30:00 hrs	09.11.2026 16:00:00 hrs

Important Instructions

1. Interested bidders shall submit their offers through email only at: **gm_rjo@cciltd.in**. The subject line shall clearly mention the Tender No. and name of work.
2. No physical offers shall be accepted. Only email offers received within the stipulated date and time shall be considered.
3. The tender documents, annexures and supporting documents shall be submitted in scanned PDF format, duly signed and stamped by the authorized signatory.
4. The bidder shall submit the following documents along with the offer:
    - Copy of GST Registration Certificate under the GST Act.
    - Duly Signed and stamped copy of complete tender documents
    - Valid laboratory recognition/NABL accreditation and scope;
    - Price Bid strictly in CCI prescribed format (Annexure-A)
5. Price Bid must be submitted only in the prescribed CCI Price Bid format. Any deviation from the prescribed format may lead to rejection of the offer.
6. The validity of the offer shall remain open for acceptance for a period of 120 days from the date of opening of the bid.
7. Tenderers are requested to visit CCI Official Website for downloading Part-I, Part-II and all related annexures. These documents form an integral part of this tender.
8. Part-I and Part-II are available in both English and Hindi versions on the website for better understanding. However, in case of any discrepancy between English and Hindi versions, the English version shall prevail.

SPECIAL TERMS AND CONDITIONS
PART -III

Tender for Calibration of 05 Nos OCEMS analysers and isokinetic stack emission monitoring/testing of Cement Mill, Kiln and Coal Mill stacks for compliance with CPCB per scope of work.

In addition to the General Terms and Conditions of tender under PART – I & II, the following special terms and conditions will also apply to the contract. These special terms and conditions, if contradictory to any conditions given in PART – I & II, will prevail upon the conditions given therein. In addition to the above, the following will also apply.

Brief description of Plant:

Rajban Cement Factory a unit of Cement Corporation of India Limited (A Govt. of India Enterprise), is an integrated cement plant having a single kiln operating on dry process technology with a clinker production capacity of 750 TPD.

1. Scope of works:

1.1 Calibration/renewal of calibration certificates of all OCEMS analysers

- The contractor shall undertake inspection, checking, calibration and/or renewal of calibration certificates of 05 Nos OCEMS analysers installed at CCI Rajban.
- Separate calibration certificate/report shall be issued for each analyser/parameter, clearly mentioning instrument identification, location, date of calibration, calibration procedure, standards/reference gases used with certificate details and validity, as applicable, observed readings, acceptance criteria, results and authorised signatory.
- The contractor shall submit all renewed calibration certificates and consolidated calibration report in hard copy and PDF. The documents shall be suitable for submission by CCI to CPCB and HPSPCB.
- All calibration work and submission of certificates shall be completed within the CPCB-prescribed period of 02 days from the actual date of resumption of operations. The bidder shall mobilise adequate manpower, instruments and reference standards to meet this mandatory timeline.

1.2 Isokinetic stack emission monitoring and PM analyser correlation

The contractor shall carry out isokinetic stack emission monitoring/testing at the following locations and parameters:

Sl. No.	Stack/location	Parameters	
1	Cement Mill Stack	Particulate Matter (PM)	Sintrol S303
2	Coal Mill Stack	Particulate Matter (PM)	Sintrol S303
3	Kiln Stack	Particulate Matter (PM)	Sintrol S303
4	Kiln Stack	NOx	LKS-1000F
5	Kiln Stack	SOx	LKS-1000F

- PM measurement shall be carried out by the isokinetic method in accordance with the applicable CPCB procedures/guidelines and relevant recognised standards/methods. The bidder shall identify the method/standard proposed in its technical offer.
- The laboratory carrying out stack emission monitoring shall be recognised under the Environment (Protection) Act, 1986 and accredited by NABL, with valid recognition/accreditation covering the relevant stack emission testing parameters and methods. A copy of the certificate and complete scope of recognition/accreditation shall be submitted with the bid and remain valid on the date of testing.
- The contractor shall provide all sampling equipment, instruments, consumables, reference standards, manpower, PPE, access arrangements and transportation required for the work. Any requirement for CCI assistance shall be identified in advance.

2. PAYMENT TERMS:

3.1 No advance payment will be made by Rajban Cement Factory under any circumstances.

3.2 100% Payment shall be released after successful completion of the respective work, submission of all required calibration certificates/test reports/correlation reports and certification of satisfactory completion by the concerned CCI department.

3.3 Income Tax TDS and other statutory deductions shall be made as applicable.

3. EARNEST MONEY DEPOSIT (EMD): NIL

4. CCI reserves the right to accept or reject any or all tenders, wholly or partly, without assigning any reason. In case of disputes, the courts having jurisdiction at Paonta Sahib, Himachal Pradesh, shall have jurisdiction, subject to the applicable CCI General Terms & Conditions.

Annexure: A

Tender No: RCF/INST/OCEMS/STACK/2026-27

(Price Bid)

Sr. No.	Description of Job	QTY	Units	Unit Rate (Rs.)	G.S.T %	G.S.T AMOUNT	TOTAL AMOUNT
		(a)		(b)	(c)	(d) = b x (c/100)	(e)=b +d
01	Inspection, calibration of OCEMS analyser(s), including applicable reference standards/gases, checks and individual certificate. (3 SPM Analyser and 01 Nos. Sox & Nox Analyser)	01	Lumsum				
	Isokinetic stack emission monitoring and PM analyser correlation – Cement Mill Stack (PM).						
	Isokinetic stack emission monitoring and PM analyser correlation – Kiln Stack (PM).						
	Isokinetic stack emission monitoring and PM analyser correlation – Coal Mill Stack (PM).						
	Stack emission monitoring/testing – Kiln Stack (NOx and SOx), in addition to PM correlation.						
	Mobilisation and transportation,						
	Note: - 1) **Certified that the GST indicated as above are as per the prevailing Act of GST and provision made there under.** 2) **The overall Lowest Bidder (L-1) shall be evaluated on the basis of net cost to the corporation.** 3) **GST applicable and payable will be paid extra. TDS of Income Tax as applicable.** 4) **Rate shall be quoted on FOR basis.** 5) **Nothing is payable other than rate quoted above.**						
	DECLARATION: - **I hereby certify that the information furnished above is true and correct to the best of my/our knowledge. I understand that in case, any deviation is found in the above statement at any stage, I/We will be blacklisted and will not have any dealing with the Department in future.**						

(Signature of Authorized Signatory with date and seal of the Company)